## Financial Bid Part-II

Name of the contractor with seal

## (A) REPAIRING CIVIL WORKS FOR 3rd'4th and 5th Floor (internal and external )only :-

Sr. no	Item	Unit	Qty	Rate (Rs)	Amount
	CIVIL WORK				
	Demolition / Clearing Works				
1.0	Demolishing 'Balcony floor' Mosaic Works of various thickness including CC base course and removal of debris for all levels	Sqm	8.36		
2.0	Demolishing RCC work for 'Balcony Arch' and disposal of unserviciable materials for all levels	Cum	11.37		
3.0	Demolishing plastering from/RCC and PCC members without causing any damage to the wall/member up to any height including disposal of debris for all level	Cum	6.29		
4.0	Dismantling and removing the existing damaged door and window frame/chowkath of different sizes without damaging the walls and removing the frame and necessary repairs to the edges of the walls for all levels	each	21		
5.0	Demolishing brick work of wall etc.(affected portion by tree roots)including stacking of serviceable materials and disposal of unserviceable materials for all levels	Cum	0		
6.0	Dismantling the damaged kitchen cabinet partition and wall lining and stacking the materials for all levels	Sqm	29.27		
7.0	Demolishing RCC work for 'Balcony floor Slab' affected by tree root and disposal of unserviceable materials for all levels	Cum	0		
8.0	Cutting and uprooting of trees and their roots in affected portions and disposal of debris for all levels	PER FLAT	13		
	TIMBER SHUTTERING				
9.0	Providing formework of ordinary timber planking including centering shuttering, strutting, propping etc, and removal of the same in-situ reinforced concrete and plain concrete work in cantilever slabs chajjas, balconies and the like as required	Sqm	29.92		
10.0	Providing formework of ordinary timber planking including centering shuttering, strutting, propping etc, and removal of the same in-situ reinforced concrete and plain concrete work in vertical sun breaker arches / slabs having curved surface as required	Sqm			
11.0	RCC WORK  Providing and claying RCC works cement, coarse sand & 20mm downgraded stone aggregate including dewatering if necessary, and curing complete excluding cost of formwork and reinforcement for cantilever slabs, chajjas, balconies - in 3rd,4th and 5th floor levels - M15 Grade concrete or prop ::	Cum	11.37		
12.0	$40~\mathrm{mm}$ thick marble chips flooring rubbed and polished to granolithic finish under layer of 32mm thick cement concrete in prop.1:2:4 and top layer 8mm thick with marble chipsof any combination of colour 1mm to 4mm	sq.m	8.36		
13.0	15mm thick cement plaster in single coat on brick walls, arches in balconies, and affected interiors etc B) b) in cement mortar 1:4	Sqm	258.19		
	Providing woodwork in frame (chowkaths) of doors/windows/clerestory windows wrought, framed and fixed in position in contact with C.C or brick masonary wall including supplying, fitting, fixing with M.S holdfast as per design embedded in cement concrete block in prop. 1:2:4 (b) with 1st class timber	Cum	0.98		
15.0	Providing fittings, fixing 1/3 panelled 2/3 glazed wooden window shutters including iron butt hinges with screws and glass panes B) with 1st class local wood (Gamari/hollock/bonsum) (1) 40mm thick	Sqm	118.28		
16.0	Providing woodwork in frame for 'kitchen cabinet' partitions/racks etc.hoisted and fixed in positions with nails, spikes etc.(b) with Gamari / Bonsum / Sundi	Sq.m	29.27		
17.0	Providing two coats of acrylic water based will putty of reputed brand over concrete / cement plaster / brick walls and ceillings after removing all loosely adhering materials	Sqm	4551.56		
18.0	Wall painting (two coats) with acrylic emulsion paint of approved brand on new and old surface complete to give an even shade after sand papered smooth (for all flats in 3rd, 4th and 5th floors)	Sqm	4551.56		
19.0	Misc, repairing works including Wash basin plumbing line, Sanitary line, Bathroom fittings etc repairing, fittings, fixing (L.S)	PER FLAT	13		
	ROOF TREATMENT				
20.0	Grading roof for water proofing treatment with  1:2:4 (cement :2 coarse sand: 4 graded stone agg.20mm nominal size) (b)Cement mortar (i)1:3(1cement:3coarse sand)	cu.m	0		
	POLISHING				
21.0	Polishing with french sprit polishing on new wood and wood based surfaces to give an even dirt, dust sand papered smooth and including a coat a wood filter	Sqm	0		
	(B) REPARING CIVIL WORKS for ALL FLOORS (external wall surface ) only				

22.0	Demolishing plastering from walls / RCC and PCC members withourt causing any damage to the wall/ member up to any height including disposal of debris for all levels for damaged portions affected by tree roots etc. only	Cum	4.50	
23.0	Providing scaffolding using L&T-Doka access scaffold system upto a height of 40m. Supported by frames of timber H-beams, bracings including suitable couplers, pins, tower spindles and 2nd class timber plank platforms complete as specified and directed by the department. (measurement to be taken on elevation area of the building / structure)	Sqm	1468.00	
24.0	15mm thick cement plaster in single coat on brick walls, arches in balconies, and affected interiors etc.B) b) in cement mortar 1:4	Sqm	340	
25.0	Finishing old/ new external wall surface with water proofing weathercoat smooth anti-fungal painting of apex brand of required shade after cleaning clearing the surface etc. at all levels (two coats)	Sqm	1040.89	
			GRAND TOTA	

IN WORDS:

SIGNATURE OF THE CONTRACTOR WITH SEAL