QUOTATION FOR COMMON FORMAT								
	ORIENTAL INSURANCE-CANTONTA							
GENERAL INTERIOR WORKS								
S.No	Description Secretary Description	Qty	Unit	Rate	Amount			
	SCHEDULE - I							
	FALSE CEILING:							
	NOTE:The false ceiling area will be measured in flat area only.							
1	Gypsum Board False Ceiling	88	Sqmt					
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising  Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspened from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids without painting, complete. (Refer the Drawings).							
2	Partly Glazed And Partly Panelled Doors.	5	Sqmt					
	II class T.W. frame of size 75 X 50 mm as per the shape and size given in the drawing. 35 mm thick (finished) flush shutter finished with 1mm laminate on both sides with necessary grooves.8mm thick clear float glass of size 250 X 1400 mm fixed with necessary steam beach beading and etching. DORMA Make hardware fittings like locking arragements,20 mm dia and 300 mm high SS brush steel finish handles, door closer,hinges, tower bolts,etc,. Fixed to the shutters. (Refer the Drawings).							
3	Full Height Partly Solid & Partly Glazed Partition:	30	Sqmt					
	Providing and fixing in position of double skin partition,partly panelled and partly glazed as per details showen in the drawing.							
	<b>Frame Work Detail</b> : Salwood frames of 50 X 50 mm, vertically at about 60 cm centers varied along columns, wall ends, junctions of walls, as necessary. Horizontally of the same size of frame at floor level, 900 mm, 2100 mm, and roof level. 50 X 25 mm at 450 mm level.							

					Page-2/2
S.No	Description	Qty	Unit	Rate	Amount
	Lining Work: MDF 8mm Commercial on both sides of framework from floor level to 900 mm level and 2100 mm level to 6" above false ceiling level finished with 1 mm laminate of approved color and shade. Between 900 mm and 2100 mm level, 8 mm thick clear float glass with etching with necessary steam beach beadings of size 35 X 10 mm. In door area 50mm x 50mm second class TW frame to be provided. (Refer the Drawings).				
	Measurement for the partition area shall be considered from the floor level to false ceiling level only.				
	Full Height Storage:	43	Sqmt		
	Providing and fixing full level storage of depth 450mm x 2133mm high comprising of MDF 18mm Commercial for top, bottom, rear, front sides and One intermediate with necessary TW reeper, fixedshelf at 75mm above FFL, adjustable shelves and opaque shutters. Side hung shutter in both the panels using MDF 18mm Commercial and finished with 1mm laminate of approved colour and shade, including all necessary TW lipping. (The shutters shall be divided into 2 units) Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc,.complete.				
	Exposed faces of comply at top and sides of unit to be finished with 1mm thick laminate of approved colour and shade.				
	All concealed faces of MDF Commercial finished with one coat of wood preservative and paint to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved colour and shade. (Refer the Drawings).& Suit the Site Conditions.	!			
	Provodining and fixing of aluminium frames 50 x 35mm for all around areas inside area provoided 10mm diaamond aluminium mesh with necessary hardware fitting etc		Sqmt		
	ESTIMATED TOTAL FOR INTERIOR WORK				0.00