

INTERIOR DECORATION WORKS FOR								
M/S ORIENTAL INSURANCE COMPANY LTD.								
Renovation of Canteen 1st floor Oriental House Head Office at A-25-27, Asaf Ali Road, New Delhi-110002.								
S.No		ITEM / WORKS	Units	Qty	RATES IN WORDS	RATES IN FIGURES	AMOUNT	TOTAL
1.00		FIRE DETECTION & ALARM SYSTEM WORKS						
a		2 Zone Oriel Series Networkable conventional fire alarm panels with 2X16 character LCD display, Battery charger, Inbuilt battery box, 12Mhz speed, Feather touch switch. (Tested By ERTL(N)) Make : Agni	NOS	1.00				
b		Optical smoke detector with remote LED output + base, Duel LED, Blinking type (UL listed) Make : System Sensor	NOS	4.00				
c		ROR cum Fixed temp. Heat Detector (57 deg. C) with remote LED output + base, Blinking type (LPCB Approved) Make : System Sensor	NOS	4.00				
d		Response Indicator. (ABS)	NOS	3.00				
e		Manual call point, MS housing.(24V)	NOS	1.00				

S.No		ITEM / WORKS	Units	Qty	RATES IN WORDS	RATES IN FIGURES	AMOUNT	TOTAL
f		Sounder, ABS housing.(24v)	NOS	2.00				
g		Copper cable 2 core 1.5 Sq. mm with Conduit & Accessories (200 meters approx estimation for Fire Alarm 11 point's.	MTR	250.00				
h		Controller	NOS	1.00				
i		Installation Charges	LS	1.00				
		TOTAL COST OF FIRE DETECTION & ALARM SYSTEM WORKS						