

INTERIOR DECORATION WORKS FOR								
M/S ORIENTAL INSURANCE COMPANY LTD.								
Renovation of Canteen 1st floor Oriental House Head Office at A-25-27, Asaf Ali Road, New Delhi-110002.								
S.No		ITEM / WORKS	Units	Qty	RATES IN WORDS	RATES IN FIGURES	AMOUNT	TOTAL
1.00		HVAC WORKS						
a		<p>Supply, Installation, testing and commissioning of Hi-wall type split air-conditioners complete with condensing unit, comprising of compressor, condenser coil , Stabilizer (Blue Bird/Luminous) and angle stand for outdoor unit . Fan motor and evaporative unit Hi wall type comprising of blower, blower motor, cooling coil etc. The unit shall be complete with inter connecting copper refrigerant pipe of what so ever length, as required per site duly insulated, refrigerant, oil, safety and operation controls, electrical switchgear and interconnecting cabling/ earthing. Drain pipe duly insulated shall be 1" dia. of upvc pipe.</p> <p>The unit shall be complete in all respect requiring only electrical connection to make it operational and shall be of following capacity.</p> <p>a) Nominal capacity : 1.5 TR Air Qty : 1360 M3/hr Type : Hi-wall , 3 star rating</p>	NOS	3.00				

S.No		ITEM / WORKS	Units	Qty	RATES IN WORDS	RATES IN FIGURES	AMOUNT	TOTAL
b		Copper pipe with electrical cable	RMT	35.00				
		Providing and laying of split ac 22 gauge soft copper pipe with electrical copper cable 2.5X4 core and its insulation as/layout.						
c		Drain pipe	RMT	20.00				
		Providing and laying of polypack upvc 25mm 20psi insulated						
		TOTAL COST OF HVAC WORKS						