

S.No		Description of Item	Unit	Quantity	Rate	Amount
1		Supply Of Hitachi Make TAKUMI 16.5 Tr ductable machines with one indoor and one out door having Single compressors and with chorded remote.	NOS	1		
2		Supply Of Hitachi Make TAKUMI 11 Tr ductable machines with one indoor and one out door having Single compressors and with chorded remote.	NOS	1		
		1 Ton 3 star Hi wall split unit	NOS	1		
		Total				
		Vat @14.5 %				
		Total Including VAT Tax				
A		LOW SIDE WORKS				
1	A	Installation of Ductable Indoor and out door units	Nos	2		
	B	Installation of Hi Wall Split units	NOS	1		
2		18 SWG Hard Drawn Suction and discharge Copper Piping with nitrile rubber insulation from indoor to outdoor units,Including Nitrogen Pressure testing.				
	A	7/8" and 1/2" for 16.5 TR	Rmt	48		
	B	1-1/8" and 7/8" for 11 TR	Rmt	15		
		1/2" and 1/4" for Split Unit	Rmt	15		
3		Insulated 25 mm dia PVC Drain Line	Rmt	20		
4		Commissioning of units	Circuits	5		
5		Supply and installation of GI Sheet Ducting fabricated out of 24&22 Gauge GI Sheet, with full threaded rods, slotted angle supports, and anchor fasteners with glass wool insulation				
	A	24 SWG	Sqm	125		
	B	22 SWG	Sqm	38		
	C	Canvass connection	NOS	2		
6		Thermal Insulation with 25 mm thick Glass wool.	Sqm	50		
7		Acoustic insulation with 12 mm thick glass wool rigid board and tissue paper	Sqm	10		
8		Supply and Fixing aluminium powder coated grill for return air and supply air				
	A	Supply Air Grill	Sqm	2		
	B	Return Air Grill	Sqm	5		
9		Supply and Fixing aluminium powder coated grill for return air and supply air				
B		Total				
		Vat @14.5 %				
		Total Including VAT Tax				
		Total Cost A+B				