

INTERIOR FURNISHING BOQ,NEW INSURANCE BRANCH AT KHANDWA,MP					
SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
<b>1</b>	<b>DISMANTLING &amp; DEMOLITION</b>				
a.	Dismantling existing Electrical fittings, wires, Data cables, fittings etc. including removal of debris from site	1.00	L.S.		-
<b>2</b>	<b>CIVIL WORKS FOR ELECTRICAL</b>	1.00	L.S.		-
	Providing & making all the works for the smooth execution of electrical works by breaking walls, cutting partitions, floors etc.				
	Rate shall include the doing good of all the areas affected with the required material.				
<b>3</b>	<b>CIVIL WORKS FOR AIR CONDITIONING</b>	1.00	L.S.		-
	Providing & making all the necessary works for the smooth execution of air-conditioning works by breaking walls, cutting partitions, floors etc.				
	Rate shall include the doing good of all the areas affected with the required material.				
<b>4</b>	<b>PANTRY PLATFORM IN JET BLACK (WITH SINK &amp; COCK)</b>	7.00	R.FT.		-
	Providing and laying platform of 2'-0" width (clear) and at 2'-8" height (top) above FFL. of approved 20 mm thick granite with bull nosed edges. It shall be supported on RCC slab with vertical brick wall supports. A 2" granite fascia should be provided below the bull nosed edge of granite platform. Rate shall be inclusive of making cutouts and polishing the edges for 18" x 18" S. S. Nirali sink without drain board (medium) or equivalent make). A flexible pipe from sink to the nahani trap shall be provided. Rate shall also include one jaguar continental C P SWAN NECK TAP with swinging casted spout (no. 347).				
<b>6</b>	<b>M.S.COLLAPSIBLE GATE</b>	48.00	S.FT		-
a.	Providing and Fixing MS Collapsible Gate Single shutter made out of vertical double channels 12mmx8mm x 3mm at maximum 125 mm apart when fully stretched as specified, braced with flat iron diagonals 12 mm x 5 mm as specified in the item. The top and bottom rails shall be of M.S. section 25mm x 25mm x 6mm with 25 mm dia rollers in every fourth double channels.				
b.	Where collapsible gate is to be fixed within the opening but is fixed along the outer surface of opening; the M.S. section at top shall be replaced by M.S. flat 40mm x 10mm. The necessary fittings such as bolts, nuts, locking arrangements, stoppers, handles, etc. shall be provided. The gates shall open and close smoothly and easily. T-iron rails shall be fixed to the lintel and floor with masonry nails embedded in cement concrete of lintel and floors at suitable spacing. The bottom runner shall be embedded with floor and proper groove formed and the floor shall be made good to match the rest of the flooring. At the sides, the end double channels shall be fixed with T-iron rails and also by holdfasts 200mm x 40mm x 4 mm bolted at one end to the end double channels and in the masonry in cement concrete 1:2:4 (nominal mix) blocks of size 115 mm x 75 mm x 230 mm, 3 nos. each side. The side masonry shall be made good to match the rest of the masonry finish. Two coats of antirusting paint to be provided to the gate.				
<b>7</b>	<b>UTILITY COUNTER (2'-0" TOP WIDE COUNTER WITH 1'-6" DEPTH STORAGE BELOW)</b>	4.75	R.FT.		-
	Providing and laying Utility Counter using 18mm thk. Comm. Ply top, sides and back, with Storage units below the counter (450mm depth). 18mm thick Comm. Ply shutter with box type hinges of approved make & steam beach lipping finished with melamine. All external surfaces to be finished in 1.0 mm laminate (suede finish) of approved make.				
	Division of shutters shall be made equally according to the length of the storage. A 18mm thk. comm. Ply shelf on battens shall be provided in middle.				
	Suitable steam beach moulding ( as advised by Branch/ Architect) 19mm x 7mm size, with melamine shall be provided to the edge of the counter top. All inner surfaces including shutters shall be finished with approved laminate.				
	Rate shall be inclusive of all necessary approved fittings like hinges, locks, 100 mm long brushed finish handles,tower bolts and any necessary hardware items.				
<b>8</b>	<b>FULL HT. STORAGE</b>	63.00	S.FT.		-
	Providing and fixing storage units of full height as per drawing. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type hinges of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages ( as approved by Branch/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make.				
	18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval ( approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
<b>9</b>	<b>PEGEON HOLE SHELVES FOR DESPATCH ROOM</b>	15.00	S.FT.		-
	Providing and fixing Pegeon Hole units of full height and 1'6" depth as per drawing. They shall be made of 18mm thk.comm. ply for both verticals and horizontal members. The bottom of the unit shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The facing edges of all ply wood sections should be provided with steam beach lipping finished with melamine with approved laminate on all the shutter edges. The size of pegeon hole to be adjusted equally as per the site condition. Approximate size of each pegeon hole should be 10" x 10" as per drawings and in consultation with Architect. All the Internal surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make.				
<b>10</b>	<b>TELLER COUNTER (3'-6" HT. ) CASH</b>	6.00	R.FT.		-

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	Providing and fixing teller counter as shown in the drwng. It shall consist of 18mm thk comm. ply. counter top & granite ledge at 3' 6" height from FFL. It consists 18mm thk. Comm. ply top as per design. 1 mm laminate(suede finish) on the table top and all facing sides. It shall be supported on 18mm thk. Comm. Ply verticals at the ends. A 18mm thk comm. Ply apron finished in 1.0 mm thick laminate (suede finish) shall be provided. 20mm thick BLACK GALAXY Granite (BR Rs. 180/s.ft) 1'-6" wide ledge with edge moulded on both sides & 6" wide protruding (edge moulded) shall be provided at 3'-6" & 3'-0" respectively from FFL. The vertical gap of 6" in between the two granite pieces should also be provided with same granite and finished neatly. 12 mm thick clear float glass with machined polished edges shall be provided from the top ledge to 5' 6" height fixed in angular on the sides with 4 1/2" gap at the bottom for teller supported on the sides by D clips.				
	1no. Computer key board tray (either ready made / made to the order as per architects design using 18mm thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic sliders( approved make), 1 no. 18mm thk. Comm. ply for Shelf below the table shall be provided for the CPU, 2 / 3 nos. (equal sized) Drawer units shall be provided as shown in drgs. Drawer shall consist of 12mm thk. Comm. Ply, sides, back & base, facia of drawers shall be of 18mm thk. Comm. Ply finished in 1 mm laminate with steam beach wooden moulding on edges of drawer units.. Each drawer shall slide on a pair of approved make telescopic drawer sliders, provision to accommodate currency notes of different denominations shall be provided on the top drawer unit, which should be finished with 1mm thick laminate. A 19mm x 7mm steam beach wooden moulding with melamine shall be provided to the edge of the table. All the exposed surfaces shall be finished with 1mm laminate all inner surfaces excluding drawers to be finished with frenchpolish and inside of the drawers with melamine finish. A 12mm thick soft board of good density to be mounted over 12mm thick comm.ply below the customer top and in between space of staff counter. The soft board to be covered with plain fabric teal green colour ( approx. cost Rs.250/mtrs) from front and edges. Rate shall be inclusive of all necessary approved fittings like locks, handle etc.				
11	<b>OVERHEAD STORAGE ABOVE UTILITY COUNTER (4.75 x2.5) &amp; IN PANTRY (7 x2.5)</b>	40.00	S.FT.		-
	Providing and fixing over-head storages which consist of 18mm thk. Comm. ply shutter with box type hinges of approved make & Steam beach lipping with approved laminate on all the edges. The shutter should be made of 18mm thk. Comm. Ply top, sides, rear and bottom. All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make.				
	Division of the shutters shall be made equally according to the length of the storage. The edges of the shutters shall be provided with steam beach lipping. One Ply shelf of 18mm thick comm.ply removable type supported on side steam beach wood battens on both sides (divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters.. Rate shall be inclusive of all necessary approved fittings like box type hinges, locks, tower bolts, 100mm SS Brush finished handle etc.				
12	<b>SHUTTERS BELOW GRANITE COUNTERS IN PANTRY (7x2.5)</b>	17.50	S.FT.		-
	Providing and fixing 19mm thk. BWR ply shutters with ply frame, skirting gap as shown in the drg. shall be maintained. Division of shutters shall be made equally according to the length of the counter.				
	Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
13	<b>MIRRORS IN TOILETS -2 Nos. (3x2)</b>	12.00	S.FT.		-
	Providing and fixing 6mm thk. of approved make clear mirror (First QUALITY) on 12mm thk. Marine ply. Mirror shall have a frame of 25mm x 25mm steam beach wooden moulding finished in melamine. The rate shall be inclusive all necessary fixtures and fittings.				
14	<b>SIDE / CORNER TABLES</b>				
a.	<b>CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)</b>	2.00	NOS.		-
b.	<b>CENTER TABLES (2'-6" X 2'-6" X 1'-6"HT)</b>	1.00	NOS.		-
	Providing and making corner / side tables of above mentioned size as per drwng. Table top shall consist of 12 mm. Thk.float glass with chamfered edge( bevelled edge) fitted to the frames with necessary arrangement. The base shall be made up of Steam beach wood frame as directed by the Branch / Architect. It should be with 4 Nos of 35mmx35mm for vertical members tied to each other with horizontal members of 20mm x 35mm frames at bottom and All wooden frames to be finished with melamine.				
15	<b>PIN-UP BOARDS (3'x5')</b>	40.00	S.FT.		-
	Providing and fixing pinup boards. It consist 12mm thick soft boards of good density to be mounted over 12mm thick comm. ply. The soft board will be covered with a plain fabric (approx Rs.250 /Rmts. of approved colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish.				
	Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately.				
16	<b>WALL MOUNTED WRITING TABLE 1'- 3" TO 1'- 6" WIDE</b>	5.00	R.FT.		-
	Providing and Fixing wall mounted writing table as per design. The top and central partitions should be with 12mm thick float glass ( approved make) with chamfered edge ( Bevelled edges) for top piece and verticals with edge polish. The glass should be supported on 18mm thick comm. ply base, rear and sides fixed to the wall. The bottom ply piece to be supported additionally with 2 Nos. of SS Brackets. The exposed faces should be finished with 1 mm thick approved laminate and the edges of ply wood to be provided with steam beach lipping finished with melamine.				

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
17	<b>DISCUSSION ROOM TABLE - (3' x 7')</b>				
	<b>IN LAMINATE FINISH</b>	1.00	NOS.		-
	Providing and making a table of over all size of top as mentioned above. It shall consist of 18mm thk. Comm. Ply top as per design (double edge on outer edge with 37mm x 10mm thk moulding with steam beach wood on the edges) supported on three boxes of size 24" x 6" made of 18mm thk. Comm. Ply inter connected with boxing 4" x 6" (as approved by branch / architect). All external surfaces to be finished in 1mm laminate of approved shade (suede)				
18	<b>TABLES (MANAGERS &amp; FRONT OFFICE)</b>				
a.	<b>BRANCH MANAGER/ RM etc. ( 5'-0" X 2'-3" )</b>	1.00	NOS.		-
b.	<b>OFFICERS ( 5'-0" X 2'-3" )</b>	4.00	NOS.		-
	Providing and laying a desk of over all size of top as mentioned. It shall consist of ¾" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on ¾" thk. Comm. Ply verticals. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. A ¾" thk. Comm. Ply apron shall be provided as per Architects design with necessary pattern. The Table top should be finished with 1.5mm Laminate (suede finish) of approved make and all other external to be finished in 1.0 mm. Thk. Laminate (suede finish). Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor position as shown in				-
	1 no. Shelf for CPU to be provided below the desk as shown in the drg. All the inner surfaces shall be finished with 1mm thick white laminate.				-
	1no. Computer key board tray (either ready made PVC Type / made to the order as per architects design using 3/4" thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic/double(Hafele/Albihari/solo make) approved sliders)				-
	A drawer unit as shown in the drg shall be provided. 3 nos of drawers with 1.0 mm. Thk. Laminate shall be provided. Height of drawers shall be 4", 4" and 11". Drawer shall consist of ½" thk. Comm. Ply sides, back and ¼" thk. Comm. Ply base. Facia of drawers shall be of ¾" thk. Comm. Ply finished in 1.0 mm. Thk. Laminate (suede finish) and with a wooden moulding on top/bottom edge for handle. 1" gap to be maintained between each drawer. Each drawer shall slide on a pair of telescopic drawer sliders(Hafele/ebco). The inside portion of draws to be finished with white laminate.				-
	Rate shall be inclusive of all necessary approved fittings like locks(Godrej make/Vijayan) for				-
19	<b>SIDE CREDENZA:</b>				
a.	<b>S1 TYPE (1'-6" DEPTH X 7'-6" LT X 2'-4.1/2" HT.) :</b>	6.00	Nos		-
b.	<b>S2 TYPE (1'-6" DEPTH X 4'-0" LT X 2'-4.1/2" HT.) :</b>	6.00	Nos		-
c.	<b>S3 TYPE (1'-6" DEPTH X 3'-6" LT X 4'-0" HT.) :</b>	4.00	Nos		-
	Providing and laying side credenzas of above mentioned sizes and as per drg. It shall consist of ¾" thk. ply top, ¾" comm. ply sides, bases and 1/2" thk. ply backs. The edge of top will be provided with a suitable (as per Architects design) wooden moulding finished with mellamine.				-
	<b>In case of S1 &amp; S2 Type, Shutters to be with:</b> A pair of ¾" comm. Ply shutters will be provided which shall slide on 1" x 1" wooden battens above skirting. 4" long SS brush finished handles to be provided in each shutter as shown in the drg. All external and internal surfaces to be finished in 1.0 mm laminate (suede finish) of approved make. There should be one adjustable shelf provided with ¾" comm. Ply pasted with laminate on both sides. All internal faces to be provided with White laminate and external surfaces with approved laminate. The All edges to be with edge banding / with suitable wooden moulding finished perfectly.				
	<b>In the case of S3 Type :-</b> Free standing side credenza of above mentioned size with openable shutters in ¾" thk. comm. ply with edge banding / with suitable wooden moulding finished perfectly. Adjustable shelves at approximately 16" C/C with ¾" thk. comm. ply laminated with white laminate on both sides and edges finished as mentioned above with all necessary fittings like 4" long SS Brushed finish handles, Tower bolts, Self Closing HAFELE MAKE hinges, GODREJ MAKE/HAFELE MAKE Locks & any miscellaneous items. The bottom facing skirting also to be finished with the same laminate as per scope drawings.				
	A ¾" thk. Fixed comm. Ply shelf on battens shall be provided at 16" intervals from the base.				-

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	Rate shall be inclusive of all necessary approved fittings like slidding roller, locks(Godrej make/Vijayan), hinges, tower bolts and any miscellaneous hardware items.				-
20	<b>BACK OFFICE RUNNING COUNTER (1'-6" WIDE)</b>	25.00	R.FT.		-
	Providing and laying a Plain running counter with only key board and Pencil Drawers at every 3' 0" length for over all size of top as mentioned below. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.5mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make.				-
	1no. Computer key board tray (either ready made / made to the order as per architects design using 3/4" thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic/double(Hafele/ebco make) approved sliders)				-
	1no. Pencil drawer unit as shown in the drg shall be provided. Drawer shall consist of 1/2" thk. Comm. Ply sides, back and 1/4" thk. Comm. Ply base. Facia of drawers shall be of 3/4" thk. Comm. Ply finished in 1.5 mm. Thk. Laminate and with a wooden moulding on top/bottom edge for handle. Each drawer shall slide on a pair of hafele make telescopic drawer sliders. Each desk shall be provided with a 3" dia PVC wire manager at the given location.				-
21	<b>SHUTTERS WITH FRAME FOR ELECTRICAL PANELS</b>	8.00	S.FT.		-
	Providing and fixing 18mm thk. Com ply shutters with same ply frame. Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finished with 2 coats of enamel paint of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch,150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills and necessary hardware fittings complete.				-
22	<b>KEY BOX</b>	1.00	NOS.		-
	Providing and fixing key box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick comm. Ply wood and lockable glass shutters in 18mm ply , with 5 mm glass. Necessary hooks to be provided inside the box. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beeding polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, locks, hooks etc. and any necessary hardware items.				-
23	<b>A.C.TRAP DOORS WITH LAMINATE FINISH</b>	0.00	S.FT.		-
	Providing and fixing A.C. Trap doors of above mentioned sizes consisting of 19mm thk. BWR ply shutters. The pair of shutters shall be with MILKY WHITE 1 mm laminate on both sides fitted in frame of 2" x 1 1/2" Sal wood sections finished with enamel paint to match with the ceiling. The frame need to be supported from the ceiling as per directions of Branch/ Architect. Rate shall be inclusive of necessary fittings like hinges ( Heavy Duty type), tower bolts, locks,				-
<b>TOTAL FOR CARPENTRY WORKS</b>					
24	<b>ENTRANCE DOORS - IN SEASONED STEAM BEACH WOOD</b>				
a.	<b>DOORS - WITH DORMA FITTINGS &amp; WITH FLOOR SPRING</b>	20.00	S.FT.		-
	Providing and fixing fully glazed doors at the main entrance as shown in the drg. Door shall consist of wooden sections steam beach wooden sections 6" x 2 " for top, bottom rails & vertical styles rails, & 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / LOGO, 1 pair of 12" long C Shaped S. S. Handles (DORMA MAKE NO:TG 9300 EQ -S 25MM DIA), floor springs(DORMA MAKE - BTS 75) & Dead Lock ( DORMA MAKE - No 778) and mellamine polish for the wood frame..				-
25	<b>MANAGER CABIN DOOR</b>				
a.	<b>IN LAMINATE FINISH - With Floor spring ( With all Hardware DORMA MAKE)</b>	0.00	S.F.T.		-
b.	<b>IN LAMINATE FINISH - With Floor spring ( With all Hardware OZONE / HAFFLE / YALE</b>	21.00	S.F.T.		-
26	<b>TOILET DOORS (2'-6" X 7'-0")</b>	2.00	Nos.		-
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3" x 1 1/2" teak wood/ steam beach section shall be provided finished in mellamine. Rate shall include approved make NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 9" SS Brushed finished, 5" hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.				-
27	<b>PANTRY DOORS (2'-6" X 7'-0")</b>	1.00	Nos.		5,000.00
	<b>PARTITIONS</b>				
	<b>Note :- The rate shall be include of frame work below false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.</b>				
a.	<b>FULLY GLAZED PARTITION - WITH TOUGHENED GLASS</b>				

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
b.	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.	60.00	Sqft.		-
28	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.	80.00	Sqft.		-
a.	<b>FULLY GLAZED PARTITION WITH FLOAT GLASS</b>				
29	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 8 mm thk. Commercial ply on both side and finished with 1.00 mm thk. Laminate / with melamine polish. The shade of laminate / polishing finish to be got approved from Branch / Architect. Approved make 10mm thick Clear Float glass to be fixed from skirting level to 2100mm level ( in the top line of Door) The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine.	50.00	Sqft.		-
30	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 8 mm thk. Commercial ply on both side and finished with 1.00 mm thk. Laminate / Veneer finished with melamine polish. The shade of laminate / veneer and polishing finish to be got approved from Branch / Architect. The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine.	85.00	Sqft.		-
a.	<b>PARTLY GLAZED PARTITION</b>				-
	<b>WITH BOTH SIDE LAMINATE - Front of BH cabin (5.58x8)</b>	<b>300.00</b>	<b>S.FT.</b>		-
31	Specification same as 3 above except for 8mm approved make clear float glass shall be provided above 2'-6" from ffl or as advised by architect with necessary steam beach moulding finished with melamine. The rate shall include necessary etching film / LOGO.				
	Specification same as 4 above but of low ht as per the drawing. A 70mm x 15mm steam beach moulding with champhered edge is to be provided on all external edges & finished in mellamine as per details. Providing and Fixing inserted Soft board / White boards / Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / Glass.				
a.	<b>PANELLING ON WALLS - with frame</b>				
33	Providing and fixing panelling on wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 25 mm @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 8mm thk. comm. Ply finished in approved 1.0 mm. Thk. Laminate / Veneer finished in melamine polish. Wooden moulding, lipping etc. as directed by Bank / architect shall be provided wherever required.				
a.	<b>PANELLING ON WALLS - With out frame</b>				
b.	<b>WITH LAMINATE -For isolated columns up to ceiling height+teller backside upto height of 5'5". (25.15 x8 + 6.83 x5.5)</b>	<b>240.00</b>	<b>S.FT.</b>		-
34	<b>FALSE CEILING AND P.O.P. WORK</b>				
	<b>FALSE CEILING - GYP BOARD</b>	<b>1,600.00</b>	<b>S.FT.</b>		-
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
35	The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. <b>Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs,</b> All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured.				
	<b>POP PUNNING</b>	<b>1,500.00</b>	<b>S.FT.</b>		-
	Providing and applying POP Punning on walls and columns (average 12mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the window and door frames. <b>If the average thickness is found to 8mm-6mm or less, then POP will be considered as pulti finish - at the rate of - 50% the quoted rate</b>				
36	<b>PAINTING</b>				

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	<b>PLASTIC EMULSION</b>	1,550.00	S.FT.		-
37	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & finish shall be provided.				
	<b>LUSTRE</b>	2,500.00	S.FT.		-
38	Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
	<b>ENAMEL PAINT (26.17x9x2x1.1)+(5x9)</b>	300.00	S.FT.		-
39	Providing & applying 1 <sup>st</sup> quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote.				
a.	<b>EXTERIOR EMULSION PAINT - UP TO 10 feet Height</b>				-
b.	<b>UP TO 10 FEET HEIGHT</b>	200.00	S.FT.		-
	<b>ABOVE 10 FEET HEIGHT &amp; SCAFFOLDING IS REQUIRED</b>	400.00	S.FT.		-
	Providing & applying exterior grade emulsion paint of approved quality, make & shade, after scrapping the surface with wire brush & then applying (minimum) 3 coats of paint as directed by Bank / Architects.				
41	<b>MISCELLANEOUS / BROUGHT OUT ITEMS</b>				
	<b>VERTICAL BLINDS WITH SCOTCH GUARD</b>	150.00	S.FT.		-
42	Providing & fixing in place 100 mm. Vertical blinds of approved make, quality and colour shade & pattern. Rate shall include necessary scotch guard treatment on both sides. The overlaps should be uniform & adequate.				
	<b>3M SYNTHETIC DOOR MATS (4'-0" x 2'-0")</b>	2.00	NOS.		-
43	Providing & laying in place Synthetic Door Mats (3M) of sizes not less than 4' x 2').				
	<b>CLOTH CURTAIN IN THE STRONG ROOM</b>	70.00	S.FT.		-
44	Providing & Fixing Curtain of approved quality and shade in the strong room fixed along with the curtain rods and all necessary fixtures and fittings complete in all respect				
	<b>FIXING THE POSTERS &amp; DANGLERS</b>	20.00	NOS.		-
45	Providing & Fixing the Poster Holders & Dangers (Supplied by the Banks Vendor) as directed by the Branch Staff / Architect on the walls/ panels / glazing etc. complete in all respect with-out spoiling the décor				
	<b>FROST FILM / ETCHING FILM OVER GLASS</b>	50.00	S.FT.		-
46	Providing and fixing etching film as directed by Branch/ Architect for excess area ( for additional area other than 1feet depth and full length of glass, along with portion spec.) to proper level, with out air bubbles / cuts / folds etc. complete.				
	<b>M.S. SLOTTED ANGLE STORAGE -5 Nos.(3x7)</b>	105.00	S.FT.		-
	Providing and making M.S. slotted angle storage using angles of 18 gauge thickness and shelves of 20 gauge designed as per the specifications of standard manufacturers. Shelves shall be provided at 1'-6" c/c & supported on frames on all four sides with vertical supports as per manufacturers' standard specifications.				
<b>IX</b>	<b>TOTAL FOR MISCELLANEOUS / BROUGHT OUT ITEMS</b>				
47	<b>BROUGHT OUT FURNITURE</b>				
a.	<b>SOFA SETS - (FABRIC COST B.R. Rs. 300/MTS. TEAL GREEN COLOUR SAMPLE TO BE GOT APPROVED)</b>				
b.	<b>SINGLE SEATER</b>	0.00	NOS.		-
c.	<b>DOUBLE SEATER</b>	1.00	NOS.		-
	<b>THREE SEATER</b>	3.00	NOS.		-
48	Providing and fixing sofa set to detail as shown in drawing about 60cm wide and about 68cm high comprising second class SAL WOOD framework using 50 x 40 with 8mm thick com plywood covering on all sides. Seats finished with spring hooked to MS plate 25mm width fixed to the seat frame. Both seat frame and back covered with layer of jute cloth and 75mm latex rubber (2 layer for seat alone) finished with 12mm foam lining and upholstered to shape with fabric (basic price Rs.300/m) for the rear of the back also and the under surface of the seat finished with Gada cloth 8mm ply below seat. <b>Note:</b> (For sofas materials like foam, latex rubber, gadacloth, spring, fabric etc., to be approved by the Architects / Branch).				
	<b>CHAIRS</b>				
A	Providing and supplying medium back chairs as per following specification (1). The chairs has a back inner / outer shell made out up of polypropylene having snap type fittings . (2). Moulded foam (48 DENSITY) is used on the seat and back. (3). A hot presses plywood seat (12 MM THICK) is used as base (4). The arm rest used is made up of soft polyurethane (250 density) having mild steel insert (5).The tilting mechanism used is having only back movement lockable at the front position. (6). The seat to back connecting mild steel plate is 10 MM thick. The handle connecting mild steel plate is 5 MM thick. (7). A seat outer made up of POLYPROPYLENE is used for asthetic appeal. ( 8). An imported gas lift mechanism is used for seat height adjustment. (9). A mild steel powder coated base (630 MM WIDE) is used having a load capacity of 800 KGS. (10). Twin wheel nylon castore are used having a load bearing capacity of 50 Kgs. Per Caster.				
B	<b>BR-IN-CHAIR ( HIGH BACK) WITH REVOLVING AND TILTING ARRANGEMENT AS PER ABOVE SPECIFICATION</b>	1.00	Nos		-
C	<b>OFFICERS/STAFF CHAIR( MEDIUM BACK) WITH REVOLVING AND TILTING ARRANGEMENT as per above specification.</b>	19.00	Nos		-
E	<b>VISITORS CHAIR /AGENT/ DISCUSSION ROOM CHAIRS - Specification same as above but the Chairs have Fixed back having no tilting mechanism . Only revolving facility would be available.</b>	11.00	Nos		-
	<b>BAR STOOL FOR PANTRY ROOM</b>	1.00	Nos		-

SR. NO	DESCRIPTION OF ITEMS- IF WORKS - KHANDWA-MP	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	<b>TOTAL FOR MISCELLANEOUS / BROUGHT OUT ITEMS</b>				
	<i>ELECTRICAL @ 10%</i>				116,900.00
	<b>ADD 18% GOODS &amp; SERVICE TAX(AS GOVT.PREVAILING RATES)</b>				
	<b>SUB TOTAL</b>				-
	<b>SAY TOTAL</b>				1,619,000.00